

Penn Valley Constructors, Inc.



Grinding down concrete



Polishing concrete

Existing concrete floor was ground down with metal bonded diamonds to 30 grit then wet polished with wet terra 220 pads and honed to a 400 grit. Floor was then sealed with concrete densifier and finished with a sequence of pads for an 800 grit finish spec. The entire floor was completed in two weeks working around the clock.



Renovated 18,000 square feet office area.

NATIONAL REFRIGERATION

Ed Caruthers, Contact
Bensalem, Pennsylvania
97,354 Square Feet
Warehouse, Manufacturing & Office
kd2 architects
Completed 2015

"Partners in Excellence"